



PUBLIC WORKS DEPARTMENT ROADS WORKPLAN FOR 2021

This plan is the work considered to be priority for 2021. Any number of things may impact the Public Works Department's ability to complete all the work proposed, e.g., weather events, emergencies, additional direction from Council throughout the season, etc. Staff shall report to Council throughout the season on the status of the work proposed. Several of these projects are very large undertakings, but all are expected to be accomplished in-house with township staff and equipment. ***materials to be used are estimated**

GOVERNMENT RD. W TO PUDDINGSTONE

Change 1 cross pipe 450mm
Reset 1 driveway entrance culvert
Replace 4 driveway entrance culvert
Ditch clean-out 700 meters
1.8 km of ripping
*30 loads of A gravel
1.8 km of hard surfacing

MARGARET STREET

Ditch clean-out 1200 meters
Prep for hard-surfacing

GOVERNMENT RD. E FROM LAKE HURON TO CIVIC #4672

Change 15 driveway entrance culverts
Change 1 cross pipe
Ditch clean-out 2 km and eliminate one cross pipe
1.7 km of ripping (prep for hard-surfacing in 2022)

CARTER SIDE RD AT GORDON LAKE RD

Change 1 cross pipe 16m x 2400mm and coupler
*80 yards of B gravel
*20 yards of A gravel
*36 yards of 4-8-inch quarry stone
Ditch clean-out 1 km on hill

GILLESPIE STREET

Ditching clean-out 100 meters
Dig out clay in road surface, replace with filter cloth and B gravel
Prep for hard-surfacing in 2022

OLD SOO RD.

Change 1 cross pipe 1200mm x 20m
60 yards of B gravel
18 yards of A gravel
Ditching clean-out on hills 2 km

OLD MILL RD.

Ditching 800 meters to eliminate water currently flooding onto road
Change 2 field entrance pipes

DIAMOND LAKE ROAD

Dig out clay frost heave about 30 meters and replace with filter cloth and B gravel
Prep same area to replace existing hard-surface area in 2022
Ditch hill at boat launch
Install new culvert

FISHER RD

Ditching 800 meters to eliminate water currently flooding onto road

PUDDINGSTONE RD AT PARK ENTRANCE

Change cross pipe 14m x 1800mm plus coupler
*60 yards of B gravel
*18 yards of A gravel

GOVERNMENT RD EAST

Change driveway entrance pipe 9m x 450mm
Change cross pipe west of Fisher Rd 16m x 450mm
Reset entrance pipe 16m x 450mm

MAINTENANCE GRAVEL

30 loads at various locations
Stockpile 20 loads of A gravel
Stockpile 20 loads of B gravel

REGULAR MAINTENANCE

Grading
Grass Cutting
Patching
When and if time permits ditching on Desbarats Lake Rd.

BRUSHING

With having our own equipment, it is hoped that the majority of brushing will be completed by spring. With current winter conditions is ideal weather and temperature to brush.

BUILDING MAINTENANCE

Staff are currently doing some long overdue inside maintenance at the water plant.